Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
7.00			7.20			7.40			7.60	1.00		7.80	3.00	
7.01			7.21			7.41			7.61	1.10		7.81	3.10	
7.02			7.22			7.42			7.62	1.20		7.82	3.20	
7.03			7.23			7.43			7.63	1.30		7.83	3.30	
7.04			7.24			7.44			7.64	1.40		7.84	3.40	
7.05			7.25			7.45			7.65	1.50	1.00	7.85	3.50	1.00
7.06			7.26			7.46			7.66	1.60		7.86	3.60	
7.07			7.27			7.47			7.67	1.70		7.87	3.70	
7.08			7.28			7.48			7.68	1.80		7.88	3.80	
7.09			7.29			7.49			7.69	1.90		7.89	3.90	
7.10			7.30			7.50	0.00		7.70	2.00		7.90	4.00	
7.11			7.31			7.51	0.10		7.71	2.10		7.91	4.15	
7.12			7.32			7.52	0.20		7.72	2.20		7.92	4.30	
7.13			7.33			7.53	0.30		7.73	2.30		7.93	4.45	
7.14			7.34			7.54	0.40		7.74	2.40		7.94	4.60	
7.15			7.35			7.55	0.50	1.00	7.75	2.50	1.00	7.95	4.75	1.50
7.16			7.36			7.56	0.60		7.76	2.60		7.96	4.90	
7.17			7.37			7.57	0.70		7.77	2.70		7.97	5.05	
7.18			7.38			7.58	0.80		7.78	2.80		7.98	5.20	
7.19			7.39			7.59	0.90		7.79	2.90		7.99	5.35	

Note .....

Computed by _____ Checked by _____

Form by M.Somkiat, October 01, 2012

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
8.00	5.50		8.20	8.50		8.40	11.50		8.60	15.50		8.80	19.50	
8.01	5.65		8.21	8.65		8.41	11.70		8.61	15.70		8.81	19.70	
8.02	5.80		8.22	8.80		8.42	11.90		8.62	15.90		8.82	19.90	
8.03	5.95		8.23	8.95		8.43	12.10		8.63	16.10		8.83	20.10	
8.04	6.10		8.24	9.10		8.44	12.30		8.64	16.30		8.84	20.30	
8.05	6.25	1.50	8.25	9.25	1.50	8.45	12.50	2.00	8.65	16.50	2.00	8.85	20.50	2.00
8.06	6.40		8.26	9.40		8.46	12.70		8.66	16.70		8.86	20.70	
8.07	6.55		8.27	9.55		8.47	12.90		8.67	16.90		8.87	20.90	
8.08	6.70		8.28	9.70		8.48	13.10		8.68	17.10		8.88	21.10	
8.09	6.85		8.29	9.85		8.49	13.30		8.69	17.30		8.89	21.30	
8.10	7.00		8.30	10.00		8.50	13.50		8.70	17.50		8.90	21.50	
8.11	7.15		8.31	10.15		8.51	13.70		8.71	17.70		8.91	21.70	
8.12	7.30		8.32	10.30		8.52	13.90		8.72	17.90		8.92	21.90	
8.13	7.45		8.33	10.45		8.53	14.10		8.73	18.10		8.93	22.10	
8.14	7.60		8.34	10.60		8.54	14.30		8.74	18.30		8.94	22.30	
8.15	7.75	1.50	8.35	10.75	1.50	8.55	14.50	2.00	8.75	18.50	2.00	8.95	22.50	2.00
8.16	7.90		8.36	10.90		8.56	14.70		8.76	18.70		8.96	22.70	
8.17	8.05		8.37	11.05		8.57	14.90		8.77	18.90		8.97	22.90	
8.18	8.20		8.38	11.20		8.58	15.10		8.78	19.10		8.98	23.10	
8.19	8.35		8.39	11.35		8.59	15.30		8.79	19.30		8.99	23.30	

Note .....

Computed by _____ Checked by _____

Hydrology Division

Royal Irrigation Department

H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
9.00	23.50		9.20	27.50		9.40	31.50		9.60	35.50		9.80	39.50	
9.01	23.70		9.21	27.70		9.41	31.70		9.61	35.70		9.81	39.70	
9.02	23.90		9.22	27.90		9.42	31.90		9.62	35.90		9.82	39.90	
9.03	24.10		9.23	28.10		9.43	32.10		9.63	36.10		9.83	40.10	
9.04	24.30		9.24	28.30		9.44	32.30		9.64	36.30		9.84	40.30	
9.05	24.50	2.00	9.25	28.50	2.00	9.45	32.50	2.00	9.65	36.50	2.00	9.85	40.50	2.00
9.06	24.70		9.26	28.70		9.46	32.70		9.66	36.70		9.86	40.70	
9.07	24.90		9.27	28.90		9.47	32.90		9.67	36.90		9.87	40.90	
9.08	25.10		9.28	29.10		9.48	33.10		9.68	37.10		9.88	41.10	
9.09	25.30		9.29	29.30		9.49	33.30		9.69	37.30		9.89	41.30	
9.10	25.50		9.30	29.50		9.50	33.50		9.70	37.50		9.90	41.50	
9.11	25.70		9.31	29.70		9.51	33.70		9.71	37.70		9.91	41.70	
9.12	25.90		9.32	29.90		9.52	33.90		9.72	37.90		9.92	41.90	
9.13	26.10		9.33	30.10		9.53	34.10		9.73	38.10		9.93	42.10	
9.14	26.30		9.34	30.30		9.54	34.30		9.74	38.30		9.94	42.30	
9.15	26.50	2.00	9.35	30.50	2.00	9.55	34.50	2.00	9.75	38.50	2.00	9.95	42.50	2.00
9.16	26.70		9.36	30.70		9.56	34.70		9.76	38.70		9.96	42.70	
9.17	26.90		9.37	30.90		9.57	34.90		9.77	38.90		9.97	42.90	
9.18	27.10		9.38	31.10		9.58	35.10		9.78	39.10		9.98	43.10	
9.19	27.30		9.39	31.30		9.59	35.30		9.79	39.30		9.99	43.30	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
10.00	43.50		10.20	47.50		10.40	52.00		10.60	57.00		10.80	62.00	
10.01	43.70		10.21	47.70		10.41	52.25		10.61	57.25		10.81	62.25	
10.02	43.90		10.22	47.90		10.42	52.50		10.62	57.50		10.82	62.50	
10.03	44.10		10.23	48.10		10.43	52.75		10.63	57.75		10.83	62.75	
10.04	44.30		10.24	48.30		10.44	53.00		10.64	58.00		10.84	63.00	
10.05	44.50	2.00	10.25	48.50	2.00	10.45	53.25	2.50	10.65	58.25	2.50	10.85	63.25	2.50
10.06	44.70		10.26	48.70		10.46	53.50		10.66	58.50		10.86	63.50	
10.07	44.90		10.27	48.90		10.47	53.75		10.67	58.75		10.87	63.75	
10.08	45.10		10.28	49.10		10.48	54.00		10.68	59.00		10.88	64.00	
10.09	45.30		10.29	49.30		10.49	54.25		10.69	59.25		10.89	64.25	
10.10	45.50		10.30	49.50		10.50	54.50		10.70	59.50		10.90	64.50	
10.11	45.70		10.31	49.75		10.51	54.75		10.71	59.75		10.91	64.75	
10.12	45.90		10.32	50.00		10.52	55.00		10.72	60.00		10.92	65.00	
10.13	46.10		10.33	50.25		10.53	55.25		10.73	60.25		10.93	65.25	
10.14	46.30		10.34	50.50		10.54	55.50		10.74	60.50		10.94	65.50	
10.15	46.50	2.00	10.35	50.75	2.50	10.55	55.75	2.50	10.75	60.75	2.50	10.95	65.75	2.50
10.16	46.70		10.36	51.00		10.56	56.00		10.76	61.00		10.96	66.00	
10.17	46.90		10.37	51.25		10.57	56.25		10.77	61.25		10.97	66.25	
10.18	47.10		10.38	51.50		10.58	56.50		10.78	61.50		10.98	66.50	
10.19	47.30		10.39	51.75		10.59	56.75		10.79	61.75		10.99	66.75	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
11.00	67.00		11.20	73.00		11.40	79.00		11.60	85.00		11.80	91.00	
11.01	67.30		11.21	73.30		11.41	79.30		11.61	85.30		11.81	91.30	
11.02	67.60		11.22	73.60		11.42	79.60		11.62	85.60		11.82	91.60	
11.03	67.90		11.23	73.90		11.43	79.90		11.63	85.90		11.83	91.90	
11.04	68.20		11.24	74.20		11.44	80.20		11.64	86.20		11.84	92.20	
11.05	68.50	3.00	11.25	74.50	3.00	11.45	80.50	3.00	11.65	86.50	3.00	11.85	92.50	3.00
11.06	68.80		11.26	74.80		11.46	80.80		11.66	86.80		11.86	92.80	
11.07	69.10		11.27	75.10		11.47	81.10		11.67	87.10		11.87	93.10	
11.08	69.40		11.28	75.40		11.48	81.40		11.68	87.40		11.88	93.40	
11.09	69.70		11.29	75.70		11.49	81.70		11.69	87.70		11.89	93.70	
11.10	70.00		11.30	76.00		11.50	82.00		11.70	88.00		11.90	94.00	
11.11	70.30		11.31	76.30		11.51	82.30		11.71	88.30		11.91	94.30	
11.12	70.60		11.32	76.60		11.52	82.60		11.72	88.60		11.92	94.60	
11.13	70.90		11.33	76.90		11.53	82.90		11.73	88.90		11.93	94.90	
11.14	71.20		11.34	77.20		11.54	83.20		11.74	89.20		11.94	95.20	
11.15	71.50	3.00	11.35	77.50	3.00	11.55	83.50	3.00	11.75	89.50	3.00	11.95	95.50	3.00
11.16	71.80		11.36	77.80		11.56	83.80		11.76	89.80		11.96	95.80	
11.17	72.10		11.37	78.10		11.57	84.10		11.77	90.10		11.97	96.10	
11.18	72.40		11.38	78.40		11.58	84.40		11.78	90.40		11.98	96.40	
11.19	72.70		11.39	78.70		11.59	84.70		11.79	90.70		11.99	96.70	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
12.00	97.00		12.20	103.50		12.40	110.50		12.60	117.50		12.80	124.50	
12.01	97.30		12.21	103.85		12.41	110.85		12.61	117.85		12.81	124.85	
12.02	97.60		12.22	104.20		12.42	111.20		12.62	118.20		12.82	125.20	
12.03	97.90		12.23	104.55		12.43	111.55		12.63	118.55		12.83	125.55	
12.04	98.20		12.24	104.90		12.44	111.90		12.64	118.90		12.84	125.90	
12.05	98.50	3.00	12.25	105.25	3.50	12.45	112.25	3.50	12.65	119.25	3.50	12.85	126.25	3.50
12.06	98.80		12.26	105.60		12.46	112.60		12.66	119.60		12.86	126.60	
12.07	99.10		12.27	105.95		12.47	112.95		12.67	119.95		12.87	126.95	
12.08	99.40		12.28	106.30		12.48	113.30		12.68	120.30		12.88	127.30	
12.09	99.70		12.29	106.65		12.49	113.65		12.69	120.65		12.89	127.65	
12.10	100.00		12.30	107.00		12.50	114.00		12.70	121.00		12.90	128.00	
12.11	100.35		12.31	107.35		12.51	114.35		12.71	121.35		12.91	128.35	
12.12	100.70		12.32	107.70		12.52	114.70		12.72	121.70		12.92	128.70	
12.13	101.05		12.33	108.05		12.53	115.05		12.73	122.05		12.93	129.05	
12.14	101.40		12.34	108.40		12.54	115.40		12.74	122.40		12.94	129.40	
12.15	101.75	3.50	12.35	108.75	3.50	12.55	115.75	3.50	12.75	122.75	3.50	12.95	129.75	3.50
12.16	102.10		12.36	109.10		12.56	116.10		12.76	123.10		12.96	130.10	
12.17	102.45		12.37	109.45		12.57	116.45		12.77	123.45		12.97	130.45	
12.18	102.80		12.38	109.80		12.58	116.80		12.78	123.80		12.98	130.80	
12.19	103.15		12.39	110.15		12.59	117.15		12.79	124.15		12.99	131.15	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
13.00	131.50		13.20	138.50		13.40	146.50		13.60	154.50		13.80	163.50	
13.01	131.85		13.21	138.90		13.41	146.90		13.61	154.95		13.81	163.95	
13.02	132.20		13.22	139.30		13.42	147.30		13.62	155.40		13.82	164.40	
13.03	132.55		13.23	139.70		13.43	147.70		13.63	155.85		13.83	164.85	
13.04	132.90		13.24	140.10		13.44	148.10		13.64	156.30		13.84	165.30	
13.05	133.25	3.50	13.25	140.50	4.00	13.45	148.50	4.00	13.65	156.75	4.50	13.85	165.75	4.50
13.06	133.60		13.26	140.90		13.46	148.90		13.66	157.20		13.86	166.20	
13.07	133.95		13.27	141.30		13.47	149.30		13.67	157.65		13.87	166.65	
13.08	134.30		13.28	141.70		13.48	149.70		13.68	158.10		13.88	167.10	
13.09	134.65		13.29	142.10		13.49	150.10		13.69	158.55		13.89	167.55	
13.10	135.00		13.30	142.50		13.50	150.50		13.70	159.00		13.90	168.00	
13.11	135.35		13.31	142.90		13.51	150.90		13.71	159.45		13.91	168.50	
13.12	135.70		13.32	143.30		13.52	151.30		13.72	159.90		13.92	169.00	
13.13	136.05		13.33	143.70		13.53	151.70		13.73	160.35		13.93	169.50	
13.14	136.40		13.34	144.10		13.54	152.10		13.74	160.80		13.94	170.00	
13.15	136.75	3.50	13.35	144.50	4.00	13.55	152.50	4.00	13.75	161.25	4.50	13.95	170.50	5.00
13.16	137.10		13.36	144.90		13.56	152.90		13.76	161.70		13.96	171.00	
13.17	137.45		13.37	145.30		13.57	153.30		13.77	162.15		13.97	171.50	
13.18	137.80		13.38	145.70		13.58	153.70		13.78	162.60		13.98	172.00	
13.19	138.15		13.39	146.10		13.59	154.10		13.79	163.05		13.99	172.50	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
14.00	173.00		14.20	183.00		14.40	193.00		14.60	203.50		14.80	215.00	
14.01	173.50		14.21	183.50		14.41	193.50		14.61	204.05		14.81	215.60	
14.02	174.00		14.22	184.00		14.42	194.00		14.62	204.60		14.82	216.20	
14.03	174.50		14.23	184.50		14.43	194.50		14.63	205.15		14.83	216.80	
14.04	175.00		14.24	185.00		14.44	195.00		14.64	205.70		14.84	217.40	
14.05	175.50	5.00	14.25	185.50	5.00	14.45	195.50	5.00	14.65	206.25	5.50	14.85	218.00	6.00
14.06	176.00		14.26	186.00		14.46	196.00		14.66	206.80		14.86	218.60	
14.07	176.50		14.27	186.50		14.47	196.50		14.67	207.35		14.87	219.20	
14.08	177.00		14.28	187.00		14.48	197.00		14.68	207.90		14.88	219.80	
14.09	177.50		14.29	187.50		14.49	197.50		14.69	208.45		14.89	220.40	
14.10	178.00		14.30	188.00		14.50	198.00		14.70	209.00		14.90	221.00	
14.11	178.50		14.31	188.50		14.51	198.55		14.71	209.60		14.91	221.65	
14.12	179.00		14.32	189.00		14.52	199.10		14.72	210.20		14.92	222.30	
14.13	179.50		14.33	189.50		14.53	199.65		14.73	210.80		14.93	222.95	
14.14	180.00		14.34	190.00		14.54	200.20		14.74	211.40		14.94	223.60	
14.15	180.50	5.00	14.35	190.50	5.00	14.55	200.75	5.50	14.75	212.00	6.00	14.95	224.25	6.50
14.16	181.00		14.36	191.00		14.56	201.30		14.76	212.60		14.96	224.90	
14.17	181.50		14.37	191.50		14.57	201.85		14.77	213.20		14.97	225.55	
14.18	182.00		14.38	192.00		14.58	202.40		14.78	213.80		14.98	226.20	
14.19	182.50		14.39	192.50		14.59	202.95		14.79	214.40		14.99	226.85	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
15.00	227.50		15.20	242.00		15.40	258.50		15.60	276.50		15.80	295.50	
15.01	228.20		15.21	242.80		15.41	259.40		15.61	277.45		15.81	296.45	
15.02	228.90		15.22	243.60		15.42	260.30		15.62	278.40		15.82	297.40	
15.03	229.60		15.23	244.40		15.43	261.20		15.63	279.35		15.83	298.35	
15.04	230.30		15.24	245.20		15.44	262.10		15.64	280.30		15.84	299.30	
15.05	231.00	7.00	15.25	246.00	8.00	15.45	263.00	9.00	15.65	281.25	9.50	15.85	300.25	9.50
15.06	231.70		15.26	246.80		15.46	263.90		15.66	282.20		15.86	301.20	
15.07	232.40		15.27	247.60		15.47	264.80		15.67	283.15		15.87	302.15	
15.08	233.10		15.28	248.40		15.48	265.70		15.68	284.10		15.88	303.10	
15.09	233.80		15.29	249.20		15.49	266.60		15.69	285.05		15.89	304.05	
15.10	234.50		15.30	250.00		15.50	267.50		15.70	286.00		15.90	305.00	
15.11	235.25		15.31	250.85		15.51	268.40		15.71	286.95		15.91	306.00	
15.12	236.00		15.32	251.70		15.52	269.30		15.72	287.90		15.92	307.00	
15.13	236.75		15.33	252.55		15.53	270.20		15.73	288.85		15.93	308.00	
15.14	237.50		15.34	253.40		15.54	271.10		15.74	289.80		15.94	309.00	
15.15	238.25	7.50	15.35	254.25	8.50	15.55	272.00	9.00	15.75	290.75	9.50	15.95	310.00	10.00
15.16	239.00		15.36	255.10		15.56	272.90		15.76	291.70		15.96	311.00	
15.17	239.75		15.37	255.95		15.57	273.80		15.77	292.65		15.97	312.00	
15.18	240.50		15.38	256.80		15.58	274.70		15.78	293.60		15.98	313.00	
15.19	241.25		15.39	257.65		15.59	275.60		15.79	294.55		15.99	314.00	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
16.00	315.00		16.20	338.00		16.40	364.00		16.60	396.00		16.80	430.00	
16.01	316.00		16.21	339.30		16.41	365.60		16.61	397.60		16.81	432.00	
16.02	317.00		16.22	340.60		16.42	367.20		16.62	399.20		16.82	434.00	
16.03	318.00		16.23	341.90		16.43	368.80		16.63	400.80		16.83	436.00	
16.04	319.00		16.24	343.20		16.44	370.40		16.64	402.40		16.84	438.00	
16.05	320.00	10.00	16.25	344.50	13.00	16.45	372.00	16.00	16.65	404.00	16.00	16.85	440.00	20.00
16.06	321.00		16.26	345.80		16.46	373.60		16.66	405.60		16.86	442.00	
16.07	322.00		16.27	347.10		16.47	375.20		16.67	407.20		16.87	444.00	
16.08	323.00		16.28	348.40		16.48	376.80		16.68	408.80		16.88	446.00	
16.09	324.00		16.29	349.70		16.49	378.40		16.69	410.40		16.89	448.00	
16.10	325.00		16.30	351.00		16.50	380.00		16.70	412.00		16.90	450.00	
16.11	326.30		16.31	352.30		16.51	381.60		16.71	413.80		16.91	452.30	
16.12	327.60		16.32	353.60		16.52	383.20		16.72	415.60		16.92	454.60	
16.13	328.90		16.33	354.90		16.53	384.80		16.73	417.40		16.93	456.90	
16.14	330.20		16.34	356.20		16.54	386.40		16.74	419.20		16.94	459.20	
16.15	331.50	13.00	16.35	357.50	13.00	16.55	388.00	16.00	16.75	421.00	18.00	16.95	461.50	23.00
16.16	332.80		16.36	358.80		16.56	389.60		16.76	422.80		16.96	463.80	
16.17	334.10		16.37	360.10		16.57	391.20		16.77	424.60		16.97	466.10	
16.18	335.40		16.38	361.40		16.58	392.80		16.78	426.40		16.98	468.40	
16.19	336.70		16.39	362.70		16.59	394.40		16.79	428.20		16.99	470.70	

Note .....

Computed by _____ Checked by _____

Hydrology Division
Royal Irrigation Department
H.38

อท.38

RATING TABLE

(เฉพาะการเตือนภัย 2560)

Name of Stream: Khlong Tha Sae | River System: Khlong Thataphao | Station: Ban Tha Sae

Province: Chumphon | Region: Southern | Code: X.64

Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.	Gage Height m.(m.s.l.)	DisCharge cms.	Differ-ence cms.
17.00	473.00		17.20	527.00		17.40	581.00		17.60			17.80		
17.01	475.70		17.21	529.70		17.41			17.61			17.81		
17.02	478.40		17.22	532.40		17.42			17.62			17.82		
17.03	481.10		17.23	535.10		17.43			17.63			17.83		
17.04	483.80		17.24	537.80		17.44			17.64			17.84		
17.05	486.50	27.00	17.25	540.50	27.00	17.45			17.65			17.85		
17.06	489.20		17.26	543.20		17.46			17.66			17.86		
17.07	491.90		17.27	545.90		17.47			17.67			17.87		
17.08	494.60		17.28	548.60		17.48			17.68			17.88		
17.09	497.30		17.29	551.30		17.49			17.69			17.89		
17.10	500.00		17.30	554.00		17.50			17.70			17.90		
17.11	502.70		17.31	556.70		17.51			17.71			17.91		
17.12	505.40		17.32	559.40		17.52			17.72			17.92		
17.13	508.10		17.33	562.10		17.53			17.73			17.93		
17.14	510.80		17.34	564.80		17.54			17.74			17.94		
17.15	513.50	27.00	17.35	567.50	27.00	17.55			17.75			17.95		
17.16	516.20		17.36	570.20		17.56			17.76			17.96		
17.17	518.90		17.37	572.90		17.57			17.77			17.97		
17.18	521.60		17.38	575.60		17.58			17.78			17.98		
17.19	524.30		17.39	578.30		17.59			17.79			17.99		

Note .....

Computed by _____ Checked by _____

Form by M.Somkiat, October 01, 2012